Town of Washington Inland Wetlands Commission

APPLICATION TO MODIFY AN APPROVED PERMIT

1. Address of Permitted Activity: 157 Calhoun Street	
2. Name of Property Owner:The Premier Trust	
3. Granted Permit # IW- <u>21 - 54</u> Approval Date: <u>11-10-2021</u> Granted for: <u>2</u>	years
 Mailing Address of Property Owner: 4465 South Jones Boulevard, Las Vegas, NV 89103 	
5. Property Owner's Phone Number: 860-354-9346 Email:	
6. Authorized Agent: Arthur H Howland & Associates, P.C. Letter of Authorization?	□No
7. Agent's Phone Number: <u>860-354-9346</u> Email: <u>pszymanski@ahhowland.co</u>	<u>m</u>
8. Brief Discussion of Permitted Activity(s): Proposed guest house that was previously approved for 778 s.f an	<u>d we are</u>
now proposing that it will be 1110 sf. with a footprint of 36 x 36. This will also include a deck/porch. A Sanitary syst	em is
proposed with other related appurtenances as shown on maps OSD.1, SDS.1 & SES.2	
9. Per Section 8.08.b of the Inland Wetlands & Watercourses Regulations please provide on a separate s	heet:
a. reasons for and nature of all proposed revisions	
b. assessment of the potential increase or diminished impact to the wetlands, watercourses, and/ the regulated area due to the proposed revision	or to
c. revised site plan or map	
d. revised sequence of construction	
e. revised erosion and sedimentation control plan (if applicable)	
f. any other pertinent information	
10. This application must be completed in its entirety, signed by the property owner and supporting documents: 1) Attached required information, 2) Yellow Mandatory Land Use Pre-Application Form signed the property owner, written approval from the conservation easement holder, if applicable, 3) Agent Authorization Letter, if applicable, and 4) \$60 Fee – per Section 9.01 of the Inland Wetlands & Watercours Regulations.	
The undersigned property owner consents to necessary and proper inspections of the above mentioned property by the IWC and/or its agent at reasonable times, both before and after action on this application.	
1-6-2022	
Signature of Property Owner (live ink) Date	
Office Use: Approved Permit: IW Fee: \$ Check # Date: Cash Received by: Date: Scanned L:\Application Packets – Scanned\Inland Wetland Forms\IWC to Modify Approved Permit	



CIVIL ENGINEERS LAND SURVEYORS SOIL SCIENTISTS LAND PLANNERS

January 5, 2022

Town of Washington, Land Use 2 Bryan Hall Plaza Washington, Connecticut 06794

Re: 157 Calhoun Street, Washington, Connecticut

Dear Commission Members,


We are formally requesting a modification to Wetlands permit #IW-21-54 for the Premier Trust, Inc. for the guest house. The guest house is going to have a footprint of 36' x 36' which will include a deck/porch. The original size was 778 s.f. and we are now proposing 1,110 s.f.


I am enclosing the revised Proposed Overall Site Development Map (OSD.1), Proposed Guest House Sanitary Plan (SDS.2) and Sedimentation & Erosion Control Plan (SES.1) for your review.


Please feel free to contact me with any questions, comments and/or concerns you may have.

Sincerely,

Paul Szymanski, P.E.







NOTE: SUBSURFACE DRAINAGE SHOULD BE INSTALLED AT

STABILIZED ANTI-TRACKING PAD.

ALL POORLY DRAINED LOCATIONS BEFORE INSTALLING THE

Helical anchor (variable depth)

Achors installed to min 1,000 ft. pounds

Boardwalk Cross Section


(Typical)

 $\frac{\text{AGGREGATE SIZE}}{2~\text{OR 3, }OR~\text{CONNECTICUT DOT 2"}}~\text{SIZE CRUSHED GRAVEL}$

CONSTRUCTION ENTRANCE

(ANTI-TRACKING PAD)

N.T.S.



PAVED AREA

SEE PAVEMENT SECTION

── COMPACTED

COMMON FILL

2. CONSTRUCT SECTION FOR ALL WATERLINES,

3. WATER LINE INSTALLATION AND STANDARD

ACCORDANCE WITH AQUARION WATER

DIMENSIONAL REQUIREMENTS SHALL BE IN

COMPANY ESTABLISHED RULES AND PROCEDURES

ANCHOR WITH TWO (2) 2"x2"x3"

EXTEND 18" INTO THE GROUND

STAKES IN EACH BALE. STAKES TO

SANITARY SEWERS & SOLID DRAINAGE PIPES.

BASE (SEE PAVEMENT SECTION)

SUBBASE BASE (SEE PAVEMENT SECTION)

FOR FULL WIDTH OF

THE TRENCH UP TO THE TOP

ROCK & 12" SAND BLANKET

OF PIPE AND 12" BELOW PIPE IN

4" SAND BEDDING BELOW THE PIPE

AND PRESHAPED TO A HEIGHT OF 10%

OF THE PIPE DIAMETER. BACKFILL WITH

LOAM AREA

4" COMPACTED

INSTALLATIONS

COMPACTED -

FINISH SUBGRADE

(WHICHEVER IS GREATER)

UTILITY TRENCH

HAY BALE INSTALLATION

AT CATCH BASINS

N.T.S.

CATCH BASIN

COMMON FILL

LOAM & SEEDED

CONSTRUCT WARNING

TAPE FOR WATER MAIN

TYPICAL HELICAL PIER DETAIL (SUPPORT FOR BOARDWALK **THROUGH WETLANDS)**

N.T.S.

SOIL EROSION AND SEDIMENTATION CONTROL PLAN

1.1 THIS PROJECT INVOLVES THE CONTRUCTION OF A SINGLE FAMILY GUEST HOUSE. OTHER IMPROVEMENTS ALSO INCLUDED AS PART OF THIS PROJECT INCLUDE THE CONSTRUCTION OF A BOARDWALK, TEMPORARY CONSTRUCTION ACCESSWAY, SUBSURFACE SEWAGE DISPOSAL SYSTEM FOR THE GUEST HOUSE AND ONE FOR THE MAIN HOUSE, GRADING, WATERCOURSE CROSSINGS, INVASIVE SPECIES REMOVAL & OTHER RELATED APPURTENANCES.

1.2 THE AREA OF THE PROJECT SITE IS APPROXIMATELY 9.2 ACRES, OF WHICH ABOUT 1.9 ACRES ARE EXPECTED TO BE DISTURBED.

1.3 SPECIAL CARE SHOULD BE TAKEN ON THIS SITE TO ENSURE THAT THE CONSTRUCTION FENCE, SILT FENCE AND/OR HAY BALES ARE REPLACED PROMPTLY IF DAMAGED.

1.4 THE CONSTRUCTION OF THE NEW GUEST HOUSE, BOARDWALK, AND RELATED APPURTENANCES ARE THE ONLY IMPROVEMENTS ASSOCIATED WITH THIS PROJECT.

1.5 ALL NECESSARY PERMITS SHALL BE ACQUIRED PRIOR TO THE START OF CONSTRUCTION.

1.6.1 SOIL EROSION AND SEDIMENT CONTROL MEASURES a. PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION, ANY NECESSARY SURVEYING TO MARK BOUNDARY

LINES AND/OR LIMITS OF CLEARING SHALL BE COMPLETED. D. EROSION CONTROL MEASURES, AS SHOWN ON THE PLAN, SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SAID MEASURES ARE TO BE MAINTAINED UNTIL ALL SITE WORK IS

BEDDING MATERIAL TO 12" ABOVE THE PIPE COMPLETED AND ALL SEEDED AREAS HAVE ESTABLISHED GROWTH.

ANY MATERIAL STORAGE PILES OUTSIDE THE IMMEDIATE CONSTRUCTION AREA SHALL HAVE A SILT FENCE OR APPROVED EQUAL SURROUNDING THEM TO CONFINE THE MATERIAL AND POSSIBLE EROSION. . THE DISTURBANCE OF LAND SHALL BE AS MINIMAL AS PRACTICABLE. RESTABILIZATION OF ALL AREAS

SHALL OCCUR AS SOON AS POSSIBLE. IF DISTURBED AREAS ARE EXPOSED FOR MORE THAN 30 DAYS, IT

SHALL BE TEMPORARILY SEEDED PER SECTION 5-3 OF THE "2002 CONNECTICUT GUIDELINES FOR SOIL

FROSION AND SEDIMENT CONTROL." AS AMENDED. IN THE EVENT THAT CONSTRUCTION OCCURS DURING

TIMES WHEN SEEDING CAN NOT BE CARRIED OUT, ERODIBLE AREAS SHALL BE MULCHED WITH HAY OR

HAVE NETTING INSTALLED AND MAINTAINED TO PREVENT EROSION. e. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE STANDARDS AND PRACTICES AS SET FORTH IN THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION

AND SEDIMENT CONTROL," AS AMENDED. f. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED DAILY. IF THE MEASURES ARE DAMAGED, THEY

SHALL BE REPAIRED AND/OR REPLACED IMMEDIATELY.

g. IN ORDER TO PREVENT EROSION, EARTH SLOPES SHALL BE 2' (HORIZONTAL) TO 1' (VERTICAL) MAXIMUM. ALL 2'(H)/1'(V) SLOPES SHALL BE STABILIZED WITH BIODEGRADABLE MATTING OR APPROVED EQUAL.

h. IN ORDER TO CONTROL SEDIMENT, TEMPORARY BARRIERS, UTILIZING STAKED HAY BALES OR SILT FENCE SHALL BE INSTALLED AS SHOWN ON THE PLAN. ANY TRAPPED SEDIMENT SHALL BE DISPOSED OF I AN ENVIRONMENTALLY ACCEPTABLE MANNER.

i. ANY REQUIRED CULVERTS OR DRAINAGE FACILITIES SHALL BE OF PROPER CONSTRUCTION SO AS TO PREVENT EROSION DURING AND AFTER CONSTRUCTION.

ADDITIONAL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED AFTER THE COMMENCEMENT OF CONSTRUCTION. THE CONTRACTOR AND A REPRESENTATIVE FROM THE TOWN SHALL BE PRESENT. 1.6.2 CONSTRUCTION NOTES AND SEQUENCE FOR CONSTRUCTION OF PROPOSED GUEST HOUSE AND

I. OBTAIN ALL NECESSARY PERMITS.

2. FLAG THE LIMITS OF CONSTRUCTION, TEMPORARY CONSTRUCTION ACCESS BASELINE, AND TREE PROTECTION AREAS. ANY TREES WITHIN CONSTRUCTION AREA THAT ARE TO BE SAVED SHOULD BE PROTECTED WITH CONSTRUCTION FENCING.

3. HOLD PRECONSTRUCTION MEETING (REMEMBER TO CALL BEFORE YOU DIG 1-800-922-4455).

4. HOLD TREE CUTTING MEETING.

5. INSTALL THE CONSTRUCTION ENTRANCE (1 DAY).

6a. INSTALL EROSION AND SEDIMENTATION CONTROLS AS SHOWN ON THE PLAN PRIOR TO CONSTRUCTION ACTIVITY. (1 WEEK) CONTACT TOWN OF WASHINGTON WETLANDS ENFORCEMENT OFFICER FOR REVIEW OF INSTALLED EROSION CONTROLS, ALLOW 48 HOURS NOTICE. 6b. ALL EROSION AND SEDIMENTATION CONTROLS ARE TO BE INSPECTED AFTER 1/4" RAIN EVENTS OR LARGER. REPAIR OR REPLACE EROSION CONTROLS AS NECESSARY (DURATION OF PROJECT).

7. INSTALL TEMPORARY CONSTRUCTION ACCESS ROAD TO PROPOSED GUEST HOUSE LOCATION. A TEMPORARY SEEPAGE ENVELOPE IS TO BE CONSTRUCTED IN THE AREA OF THE WETLANDS CROSSING. INSTALL THE 24" CPP TO ALIGN WITH THE EXISTING WATERCOURSE. (2 WEEKS)

8. CUT TREES WITHIN THE DEFINED CLEARING LIMITS AND REMOVE CUT WOOD. CHIP BRUSH AND SLASH, STOCKPILE CHIPS FOR FUTURE USE OR REMOVE OFF SITE (1 WEEK).

9. EXCAVATE ALL STUMPS LOCATED IN THE STRUCTURAL AREA AND REMOVE TO A DISPOSAL SITE OR STOCKPILE AREA TO BE CHIPPED. STUMPS IN NON-STRUCTURAL AREAS MAY BE GROUND IN PLACE OR CUT FLUSH WITH THE GROUND LEVEL AND LEFT IN PLACE IN ACCORDANCE WITH THE PLANS (1 WEEK).

10. STRIP ALL TOPSOIL WITHIN THE SLOPE LIMITS, STOCKPILE ALL TOPSOIL IN AN APPROVED AREA AND SECURE WITH EROSION AND SEDIMENT CONTROLS (1 WEEK). 11. MAKE ALL CUTS AND FILLS REQUIRED. ESTABLISH THE SUBGRADE FOR THE TOPSOIL AREAS AND

PATHS. BENCH THE PROPOSED HOUSE AREA TO A SUBGRADE. ALLOW A REASONABLE AMOUNT OF AREA AROUND THE FOOTPRINT OF THE HOUSE FOR THE CONSTRUCTION ACTIVITIES (1 WEEK). 12. BEGIN CONSTRUCTION OF THE GUEST HOUSE. INSTALL SEPTIC SYSTEM AND WELL. PERMANENTLY

SEED SEPTIC AREA IMMEDIATELY AFTER INSTALLATION. WITHIN TWO WEEKS OF ROOF COMPLETION, STONE SPLASH/INFILTRATION TRENCH SHALL BE INSTALLED SO THAT THE RUNOFF CAN BE APPROPRIATELY HANDLED PER THE PLAN. (6 MONTHS). 13. BEGIN CONSTRUCTION OF THE BOARDWALK, HELICAL PIER INSTALLATION AND BOARDWALK

CONSTRUCTION SHOULD OCCUR DURING PERIOD IN WHICH THERE IS NO RAINFALL 48 HOURS PRIOR AND NO RAINFALL FORECAST 72 HOURS AFTER COMMENCEMENT (2 WEEKS). BOARDWALK IS TO BE CONSTRUCTED USING HELICAL PIERS.

14. CONSTRUCT DRAINAGE PER PLANS. INSTALL ALL UNDERGROUND UTILITIES TO WITHIN 5 FEET OF THE HOUSE AT THIS TIME (1 WEEK). UTILITIES ARE TO BE CONNECTED TO THE BOARDWALK WHEN CROSSING THE WETLANDS WITH ADEQUATE PROTECTION.

15. PREPARE SUB-BASE, SLOPES, PATHWAYS, AND ANY OTHER DISTURBANCE FOR FINAL GRADING (1

16. APPLY FINISHED SURFACE TO PATHWAYS. (1 WEEK).

17. PLACE TOPSOIL WHERE REQUIRED. COMPLETE ANY PROPOSED PERIMETER LANDSCAPE PLANTINGS (

18. FINE GRADE, RAKE, SEED, AND MULCH (1 WEEK).

19. UPON SUBSTANTIAL COMPLETION OF THE GUEST HOUSE, COMPLETE THE BALANCE OF SITE WORK AND APPLY STABILIZATION MEASURES (I.E. TOPSOIL, SEEDING, SODDING, MULCHING, ETC.) TO DISTURBED AREAS. FOLLOW SECTION 5-3 OF THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL (1 WEEK).

20. INSPECT AND CLEAN DRAINAGE AS NEEDED (1 DAY).

21. CLEAN UP ANY TRAPPED SEDIMENT AND PLACE IN AN AREA THAT WILL ALLOW IT TO BLEND INTO THE LANDSCAPE. REMOVE SES CONTROLS AT PROPER TIMES. (ONLY AFTER ALL CONSTRUCTION AREAS ARE STABILIZED.) (1 DAY)

22, REMOVE TEMPORARY CONSTRUCTION ACCESS ROAD WORKING FROM THE GUEST HOUSE TO WETLANDS. REMOVE THE SEEPAGE ENVELOPE, 24" CPP AT THE WATERCOURSE CROSSING AND TEMPORARY ACCESS WAY THROUGH THE WETLANDS. RESTORE ALL DISTURBED AREAS.

23. REMOVE INVASIVE SPECIES AS PER PLANS. SEE ADDITIONAL INVASIVE SPECIES NOTES ON SHEET SES.2. INSTALL PROPOSED PLANTINGS PER LANDSCAPE ARCHITECT PLAN. (2 WEEKS)

24. CONSTRUCT PROPOSED SEPTIC SYSTEM TO SERVE THE MAIN HOUSE AND GARAGE. DISCONNECT THE EXISTING SEPTIC SYSTEM, PUMP AND CRUSH/REMOVE EXISTING MAIN HOUSE SEPTIC SYSTEM. COMPLETE FINAL GRADING, SEED AND HAY. (3 WEEKS)

25. AFTER SEPTIC AREA IS STABILIZED, REMOVE TEMPORARY CONSTRUCTION ACCESS WAY BACK TO THE ROAD. RESTORE ALL DISTURBED AREAS AND STABILIZE. (1 WEEK)

26. AFTER ALL DISTURBED AREAS ARE STABILIZED, REMOVE TEMPORARY PERIMETER EROSION CONTROLS (I.E. SILT FENCE, HAYBALES, ETC.) (3 DAYS)

SURVEYORS PLANNERS HUR

COPIES NOT BEARING THE EMBOSSED SEAL OF

THE SURVEYOR OR ENGINEER SHALL BE

REVISIONS TO THESE PLANS BY ANYONE

OTHER THAN ARTHUR H. HOWLAND, PC SHALL

HOWLAND, PC SHALL TAKE NO RESPONSIBILITY

REVISED 11/5/2021 PER WETLANDS COMMENTS

MAKE THESE PLANS NULL AND VOID. ARTHUR H.

RENDERED NULL AND VOID.

FOR SAID REVISIONS.

Proposed Sedimentation & **Erosion Control Details**

The Premier Trust Inc.

Tax Map 5 Block 10 Lot 20

Area = 402,644 S.F. / 9.243 Ac.

157 Calhoun Street **Town of Washington** County of Litchfield **State of Connecticut**

October 22, 2021

N.T.S.

